# Vertiv<sup>™</sup> PowerGo rPDU



# **OVERVIEW**

Switched Unit Level rPDUs provide reliable power distribution to critical IT equipment while delivering individual outlet level control and a comprehensive view of input power usage via remote network access.

#### **Benefits**

- Remotely reboot outlets to power cycle unresponsive IT equipment or increase runtime of critical equipment upon power failure with outlet-level control.
- Reliable power distribution with local • and remote power monitoring options offer quick access to critical power usage information to evaluate energy usage trends and maximize uptime.
- Fault-Tolerant Daisy Chaining with . RSTP simplifies intelligent rPDU connectivity and ensures data is reported even when a break in the network chain occurs.
- Standard 1 year warranty.

### 

## Part #: EP5G80A0

曰

Model Number: VC2HAF0A20B4DXX? Category: Switched Sub Category: Unit Level Monitoring Power Configuration: 16A, 230V, 3.6kW Physical Configuration: 66in / 1683mm, Vertical

**Product Summary:** 


rPDU - Switched Unit Level, 16A, 230V, 3.6kW, 0U Vertical, (20) Manual locking IEC C13, (4) Manual locking IEC C19, 3m power cord with 1P + N + E, Black Powder Coat

Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA © Vertiv Group Corp. All rights reserved. Vertiv<sup>™</sup>, and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here. Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's componence.

### Monitoring:

Input power monitoring with Outlet switching. Phase level current monitoring. Daisy chain Ethernet connectivity. Local high visibility LED display.

#### **Receptacle:**



### **Product Specification and Options**

#### **System Features**

Ionitoring	Input power monitoring with Outlet switching. Phase level
	current monitoring. Daisy chain Ethernet connectivity. Local high visibility LED display.
Ionitoring Level 1	Aggregate - Total Unit Monitoring (kWh, W, VA, PF)
Ionitoring Level 2	Phase (A, B, C) Monitoring (kWh, W, VA, PF, V, A)
Remote Power Management	Individual Outlet Switching with Optional User Defined Time Delays and Sequential Power-up
Quantity Of Inputs	1
/oltage	230V
Current	16A
A per Input (Load Capacity)	3.6kW
requency	50/60Hz
Over Current Protection	None
witch	No
crolling / Rotatable Digital Display	Yes
Power Cable Wire Gauge	2.5mm² H05VVF
Power Cable Length	10ft / 3m
lug Туре	IEC60309 1P + N + E, 16A, 250V, Splashproof IP44
Receptacle/Socket Type #1	Manual Locking IEC C13
Quantity on Face	20
Maximum Output per Receptacle/Socket	10A
Voltage per Receptacle/Socket	230V
Receptacle/Socket Type #2	Manual Locking IEC C19
Quantity on Face	4
Maximum Output per Receptacle/Socket	16A
Voltage per Receptacle/Socket	230V
letwork Connection	Dual 10/100Mbps Ethernet
Protocols Supported	DHCP, HTTP, HTTPS, IPv4, IPv6, LDAP, NTP, RADIUS, RSTP, SSH, SMTP, SNMP (v1/v2c/v3), Syslog, TACACS+, Modbus TCP
Data Access Formats	CSV datalog, JSON API, JSON datalog
P Reset Button	Yes
lard Reboot Button	Yes
laximum Operating Temperature	45C / 113F

Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA © Vertiv Group Corp. All rights reserved. Vertiv", and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here. Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.

Heavy Steel - Powder Coat Finish	Black
Configuration	Zero U
Product Warranty	One Year
Certification/Agency Approvals	CE Marked
Certification/Agency Approvals	Complies with IEC 62368-1 (DOC Available)
Certification/Agency Approvals	Complies with EN 55032 and EN 55035
Certification/Agency Approvals	RoHS Compliant
Certification/Agency Approvals	FCC Marked
Chassis Dimensions (LxWxD)	1683mm x 58mm x 77mm
Shipping Weight	10.5 kg

Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA © Vertiv Group Corp. All rights reserved. Vertiv ", and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here. Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.