Vertiv[™] PowerIT rPDU



OVERVIEW

Upgradeable Switched Unit Level Monitored rPDUs provide reliable power distribution to critical IT equipment while delivering individual outlet level control and a comprehensive view of input power usage via remote network access. Includes environmental monitoring capabilities to obtain realtime environmental metrics. Upgrade the hot-swappable monitoring device on select units to leverage new technologies and accommodate changing business needs.

Benefits

- Remotely reboot outlets to power cycle unresponsive IT equipment or increase runtime of critical equipment upon power failure with outlet-level control.
- Reliable power distribution with local and remote power monitoring options offer quick access to critical power usage information to evaluate energy usage trends and maximize uptime.
- Environmental monitoring capabilities with the addition of optional environmental sensors ensure users have critical infrastructure data at their fingertips to prevent climate-related equipment failure and system downtime.
- Fault-Tolerant Daisy Chaining with RSTP simplifies intelligent rPDU connectivity and ensures data is reported even when a break in the network chain occurs. Supports up to 40 rPDUs.
- Daisy-chain up to 50 devices on a single IP address and reduce

Part #: VP5N30AM

Model Number: MNS5MGW1-36PT68-3TL15A0A10-S-A Category: Switched Sub Category: Unit Level Monitoring Power Configuration: 30A, 208V DELTA, 8.6kW Physical Configuration: 72in / 1829mm, Vertical

Product Summary:

rPDU, Switched Unit Level Monitoring EC, 30A, 208V Delta, 8.6kW, Vertical, (30) Locking IEC C13, (6) Locking IEC C19, 10ft / 3m power cord with L15-30P, Black Powder Coat.

Monitoring:

Input power monitoring with Outlet switching. Circuit/Breaker current monitoring. Environmental monitoring via optional remote sensors. Daisy chain Ethernet connectivity. Local high visibility display.

Plug Form:



L15-30F



Receptacle:

Locking IEC C13 (Quantity: 30)

Locking IEC C19 (Quantity: 6)

Chassis Color Options:



To discuss color options, contact your local sales representative.

Product Specification and Options

System Features

```
Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA
```

Vertiv Group Corp. All rights reserved. Vertiv^{*}, and the Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv^{*} Sign of Vertiv^{*} Group Corp. All rights and the second and t

deployment time with selfconfiguration of downstream devices.

| Monitoring | Input power monitoring with Outlet switching. Circuit/Breaker |
|--|---|
| | current monitoring. Environmental monitoring via optional remote sensors. Daisy chain Ethernet connectivity. Local high visibility display. |
| Innut Monitoring | Total Unit Monitoring (kWh, W, VA, PF) |
| Input Monitoring | Phase (AB, BC, CA) Monitoring (kWh, W, VA, PF, V, A) Line (A, B, C) Monitoring (A) |
| | Power Measurements Compliant with ANSI C12.1 and IEC 62053- 21 at 1% Accuracy Class Requirements |
| Circuit Monitoring | Circuit / Breaker Monitoring (A) |
| | Circuit/Breaker Current Measurements Independently Tested and Verified at 1% Accuracy |
| Remote Power Management | Individual Outlet Switching with Optional User Defined Time Delays and Sequential Power-up |
| Quantity Of Inputs | 1 |
| Voltage | 200-240V Delta |
| Current | 30A x 3 Phase DELTA |
| VA per Input (Load Capacity) | 8.6kW (208V) |
| Frequency | 50/60Hz |
| Over Current Protection | (3) 20A Double Pole Magnetic Breakers (10kAIC Rated) |
| Switch | Breaker/Switch Combination |
| LCD Touchscreen Display / Auto Oriented | Yes |
| Indicators - LED(s) | 36 |
| Power Cable Wire Gauge | 10/4 |
| Power Cable Length | 10ft / 3m |
| Power Entry Location | Bottom Front |
| Ріид Туре | NEMA L15-30P Twistlock |
| Combined Total Receptacle/Socket Quantity | 36 |
| Alternating Phase/Circuits | Yes |
| Receptacle/Socket Type #1 | U-Lock IEC C13 |
| - Quantity on Face | 30 |
| - Quantity per Breaker and Phase Combination | 10 |
| - U-Lock Color ID | 3 Circuit = Orange, Green, Blue |
| - Style | Individual |
| - Voltage per Receptacle/Socket | 208V |
| Receptacle/Socket Type #2 | U-Lock IEC C19 |
| - Quantity on Face | 6 |
| - Quantity per Breaker and Phase Combination | 2 |
| - U-Lock Color ID | 3 Circuit = Orange, Green, Blue |
| - Style | Individual |
| - Voltage per Receptacle/Socket | 208V |
| Network Connection | Dual 10/100/1000Mbps Ethernet |
| Protocols Supported | DHCP, HTTP, HTTPS, IPv4, IPv6, LDAP, NTP, RADIUS, RSTP, SSH, SMTP, SNMP (v1/v2c/v3), Syslog, TACACS+, Modbus TCP |
| Data Access Formats | CSV datalog, JSON API, JSON datalog |

Vertiv Group Corp. All rights reserved. Vertiv[™], and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here. Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.

| USB Support | Yes |
|--|--|
| IP Reset Button | Yes |
| Hard Reboot Button | Yes |
| Serial Connection | RS232 via RJ45 |
| Remote Sensor RJ Connection Jacks | 1 (Supports up to 16 Sensors) |
| Maximum Operating Temperature | 60C / 140F |
| Heavy Steel - Powder Coat Finish | Black |
| Configuration | Zero U |
| 7938 Vertical Mounting Bracket Kit | Yes |
| Toolless Mounting Hardware - Center to Center Spacing | 61.25in and 64.75in / 1556mm and 1645mm |
| Country of Origin | USA, TAA Compliant and Buy American Act COTS Compliant |
| Product Warranty | 5-year limited warranty |
| Certification/Agency Approvals | UL & c-UL Listed 62368-1 |
| Certification/Agency Approvals | RoHS Compliant |
| Certification/Agency Approvals | FCC Part 15 Class A Conformance |
| Chassis Dimensions (LxWxD) | 72in x 2in x 2.6in / 1829mm x 51mm x 66mm |
| Doghouse (D) | 1.4in / 36mm |
| Shipped Weight | 22lbs (9.98kg) |
| | |

Vertiv.com | Vertiv Headquarters, 505 N. Cleveland Avenue, Westerville, OH, 43082, USA © Vertiv Group Corp. All rights reserved. Vertiv ", and the Vertiv logo are trademarks or registered trademarks of Vertiv Group Corp. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness here. Vertiv Group Corp. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications, rebates and other promotional offers are subject to change at Vertiv's sole discretion upon notice.